

Formularul C5

PERSOANA JURIDICA ACHIZITOARE (INVESTITOR)
PRIMARIA MUNIC.HUSI

Lucrarea: 054-REPAR.CURENTE GRAD.NR.3 HUSI

Obiectul: 001-REPARATII CURENTE GRADINITA

Categoria de lucrari: 01-LUCRARI CONSTRUCTII

LISTA CUPRINZAND CANTITATILE DE LUCRARI

Nr. crt.	Capitolul de lucrari Simbol Denumire resursa Observatii Corectii Liste anexe	U/M	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare
0	1	2	3	4	5
1	CF10C1	82 MP	164,00000	2,11 11,40	346,42 1869,60
	GLET DE IPSOS APLICAT LA TENCUERILE INTERIOARE DRIS CUTE:			0,03 0,00	4,10 0,00
				13,54	2220,12
2	CN04C1	82 MP	329,60000	4,49 24,00	1478,26 7910,40
	VOPSITORII LA INTERIOR SI EXTERIOR EXECUT MANUAL CU VAR LAVABIL PE GLET DE NETEZIRE EXISTENT			0,00 0,00	0,00 0,00
				28,49	9388,66
	L:10161 -M :8881126	-VAR LAVABIL			
3	RPCT30B1	82 MP	172,00000	0,00 8,50	0,00 1462,50
	DESFACEREA LAMBRIURILOR EXECUTATE DIN PLACI MELAMI NATE DIN RFL.			0,00 0,00	0,00 0,00
				8,50	1462,50
4	CK17E	99 MP	172,00000	40,95 25,00	7042,84 4300,00
	LAMBRIURI LA PERETI EXEC. PE SANTIER, DIN PROFILURI DE MASE PLASTICE (EVC)			0,20 0,00	34,40 0,00
				66,15	11377,24
	L:LC09N -0002:6102817	-CHIT DE ETANS.SILICON KODISEL HAC			
5	SC18A6	82 BUCATA	5,00000	31,88 8,40	159,40 42,00
	RAMA PENTRU VAS DE CLOSET, DIN BACHELITA CU CABAC			0,00 0,00	0,00 0,00
				40,28	201,40
6	SC16F1	82 BUCATA	5,00000	140,17 56,40	700,83 282,00
	REZERVOR PT SPALARE VAS WC DIN PORTELAN TIP R2 MON T. LA SEMIINALTIME CU DIBLURI METALICE			0,00 0,00	0,00 0,00
				196,57	982,83
7	RPCK14B	99 M	135,00000	8,22 6,00	1110,18 810,00
	PLINTE PVC LA PERETI GATA TENCUITE, LIPITE CU ADEZI V PRENADEZ IN CAMERE			0,02 0,00	3,04 0,00
				14,25	1923,22
	L:LC62E -0030:6718362	-PROFILE PVC PLASTIFIAT BAGHETA PT. PLINTA MD1 80X2 MM			
8	RPIZB63A	99 M	135,00000	0,00 4,00	0,66 540,00
	DESFACERE PLINTE LA PERETI, SOCLURI, POSTAMENTE H < 150 MM			0,02 0,00	3,04 0,00
				4,03	543,70

Formularul C5

Execuțan0013	Obiectiv054	Obiect001	Categ01			
0	1	2	3	4	5	
9.	RPEE17A	99 BUCATA	7,00000	9,10	63,67	
				13,20	92,40	
				0,00	0,00	
				0,00	0,00	
				22,30	156,07	
	L:EL03F -0032:7319280	-DOZE PT. APARATE PT. TUBURI IZOLANTE USOR PROTEJATE -AIP				
	L:EL18M -0115:5536157	-PRIZA BIPOLARA BACHEL. CU CONT. PROT. MARIT APAR 250/10A				
10.	RPEF11F3	82 BUCATA	10,00000	60,30	602,95	
				50,40	504,00	
				0,00	0,00	
				0,00	0,00	
				110,70	1106,95	
	L:12009 -0015:5102580	-CORP IL. FL. FIA -01 240 220V ZX 40W CS				
11	RPEE02A1	82 BUCATA	10,00000	9,12	91,15	
				13,50	135,00	
				0,00	0,00	
				0,00	0,00	
				22,62	226,15	
	L:12011 -0004:5520392	-COMUTATOR MANUAL 10A MONTAT INGROPAT				
TOTALA:					11.596,35	
					17.947,90	
					44,58	
					0,00	
					29.588,82	

INTOCMIT
ING. DORNEANU EMILIAN



Executant: 0013

Obiectiv 054

Obiect 001

Categorie 01

REPAR. CURENTE GRAD. NR. 3 HUSI

REPARATIILE CURENTE GRADINITA

LUCRARI CONSTRUCTII

Recapitulatie

[ron]

	Coeficient	Material		Manopera	Utilaj	Total
		A	B	C	D	
1) Total A=Cheltuieli directe		11596.35	17947.90	44.58	29588.82	
a Transp,manip,aprov;	A* 0.00000	0.00			0.00	
b Transp.auto	0.00* 1.00000	0.00			0.00	
c Tr.gara-santier	1.91* 0.00	0.00			0.00	
d C.A.M.	B* 0.02250				403.83	
TOTAL B=Cheltuieli directe		11596.35	17947.90	44.58	29992.65	
e Cheltuieli indirecte	TotB* 0.10000				2999.26	
f Profit	(Tot+e)B* 0.10000				3299.19	
Total cheltuieli					36291.10	
T.V.A.	0.19000				6895.31	
TOTAL DEVEZ ANALITIC					43186.41	

INTOCMIT

ING. DORNEANU EMILIAN

Președinte de ședință,
Cristinel Popa



Secretar general,
jr. Monica Dumitrașcu

